MITIGATION MONITORING PROGRAM

Section 21081.6 of the Public Resources Code requires a Lead Agency to adopt a "reporting or monitoring program for the changes made to the project or conditions of project approval, adopted in order to mitigate or avoid significant effects on the environment" (Mitigation Monitoring Program, Section 15097 of the *CEQA Guidelines* provides additional direction on mitigation monitoring or reporting). This Mitigation Monitoring Program (MMP) has been prepared in compliance with the requirements of CEQA, Public Resources Code Section 21081.6, and Section 15097 of the CEQA Guidelines. The City of Los Angeles is the Lead Agency for this project.

A Mitigated Negative Declaration (MND) has been prepared to address the potential environmental impacts of the Project. Where appropriate, this environmental document identified Project design features, regulatory compliance measures, or recommended mitigation measures to avoid or to reduce potentially significant environmental impacts of the Proposed Project. This Mitigation Monitoring Program (MMP) is designed to monitor implementation of the mitigation measures identified for the Project.

The MMP is subject to review and approval by the City of Los Angeles as the Lead Agency as part of the approval process of the project, and adoption of project conditions. The required mitigation measures are listed and categorized by impact area, as identified in the MND.

The Project Applicant shall be responsible for implementing all mitigation measures, unless otherwise noted, and shall be obligated to provide documentation concerning implementation of the listed mitigation measures to the appropriate monitoring agency and the appropriate enforcement agency as provided for herein. All departments listed below are within the City of Los Angeles unless otherwise noted. The entity responsible for the implementation of all mitigation measures shall be the Project Applicant unless otherwise noted.

As shown on the following pages, each required mitigation measure for the proposed Project is listed and categorized by impact area, with accompanying discussion of:

Enforcement Agency – the agency with the power to enforce the Mitigation Measure.

Monitoring Agency – the agency to which reports involving feasibility, compliance, implementation and development are made, or whom physically monitors the project for compliance with mitigation measures.

Monitoring Phase – the phase of the Project during which the Mitigation Measure shall be monitored.

- Pre-Construction, including the design phase
- Construction
- Pre-Operation
- Operation (Post-construction)

Monitoring Frequency – the frequency of which the Mitigation Measure shall be monitored.

Action Indicating Compliance – the action of which the Enforcement or Monitoring Agency indicates that compliance with the required Mitigation Measure has been implemented.

The MMP performance shall be monitored annually to determine the effectiveness of the measures implemented in any given year and reevaluate the mitigation needs for the upcoming year.

It is the intent of this MMP to:

Verify compliance of the required mitigation measures of the EIR;

Provide a methodology to document implementation of required mitigation;

Provide a record and status of mitigation requirements;

Identify monitoring and enforcement agencies;

Establish and clarify administrative procedures for the clearance of mitigation measures;

Establish the frequency and duration of monitoring and reporting; and

Utilize the existing agency review processes' wherever feasible.

This MMP shall be in place throughout all phases of the proposed Project. The entity responsible for implementing each mitigation measure is set forth within the text of the mitigation measure. The entity responsible for implementing the mitigation shall also be obligated to provide certification, as identified below, to the appropriate monitoring agency and the appropriate enforcement agency that compliance with the required mitigation measure has been implemented.

After review and approval of the final MMP by the Lead Agency, minor changes and modifications to the MMP are permitted, but can only be made by the Applicant or its successor subject to the approval by the City of Los Angeles through a public hearing. The Lead Agency, in conjunction with any appropriate agencies or departments, will determine the adequacy of any proposed change or modification. The flexibility is necessary in light of the proto-typical nature of the MMP, and the need to protect the environment with a workable program. No changes will be permitted unless the MMP continues to satisfy the requirements of CEQA, as determined by the Lead Agency.

MITIGATION MONITORING PROGRAM

Aesthetics

I-10 Aesthetics (Landscape Plan)

Environmental impacts to the character and aesthetics of the neighborhood may result from project implementation. However, the potential impacts will be mitigated to a less than significant level by the following measure:

All landscaped areas shall be maintained in accordance with a landscape plan, including an automatic irrigation plan, prepared by a licensed landscape architect in accordance with LAMC Sections 12.40 and 12.41. The final landscape plan shall be reviewed and approved by the City of Los Angeles Department of City Planning during the building permit process.

Enforcement Agency: Los Angeles Department of City Planning (plan review); Los Angeles Department of Building and Safety (operation)

Monitoring Agency: Los Angeles Department of City Planning (plan review); Los Angeles Department of Building and Safety (operation and maintenance)

Monitoring Phase: Pre-construction; Construction

Monitoring Frequency: Once, at plan check for Project; Once, during field inspection

Action Indicating Compliance: Plan approval and issuance of applicable building permit (Preconstruction); Issuance of Certificate of Occupancy of Use of Land (Construction)

Biology

IV-20 Habitat Modification (Nesting Native Birds, Non-Hillside or Urban Areas) The project will result in the removal of vegetation and disturbances to the ground and therefore may result in take of nesting native bird species. Migratory nongame native bird species are protected by international treaty under the Federal Migratory Bird Treaty Act (MBTA) of 1918 (50 C.F.R Section 10.13). Sections 3503, 3503.5 and 3513 of the California Fish and Game Code prohibit take of all birds and their active nests including raptors and other migratory nongame birds (as listed under the Federal MBTA).

 Proposed project activities (including disturbances to native and non-native vegetation, structures and substrates) should take place outside of the breeding bird season which generally runs from March 1- August 31 (as early as February 1 for raptors) to avoid take (including disturbances which would cause abandonment of active nests containing eggs

- and/or young). Take means to hunt, pursue, catch, capture, or kill, or attempt to hunt, pursue, catch, capture of kill (Fish and Game Code Section 86).
- If project activities cannot feasibly avoid the breeding bird season, beginning thirty days prior to the disturbance of suitable nesting habitat, the applicant shall:
 - a. Arrange for weekly bird surveys to detect any protected native birds in the habitat to be removed and any other such habitat within properties adjacent to the project site, as access to adjacent areas allows. The surveys shall be conducted by a qualified biologist with experience in conducting breeding bird surveys. The surveys shall continue on a weekly basis with the last survey being conducted no more than 3 days prior to the initiation of clearance/construction work.
 - b. If a protected native bird is found, the applicant shall delay all clearance/construction disturbance activities within 300 feet of suitable nesting habitat for the observed protected bird species until August 31.
 - c. Alternatively, the Qualified Biologist could continue the surveys in order to locate any nests. If an active nest is located, clearing and construction within 300 feet of the nest or as determined by a qualified biological monitor, shall be postponed until the nest is vacated and juveniles have fledged and when there is no evidence of a second attempt at nesting. The buffer zone from the nest shall be established in the field with flagging and stakes. Construction personnel shall be instructed on the sensitivity of the area.
 - d. The applicant shall record the results of the recommended protective measures described above to document compliance with applicable State and Federal laws pertaining to the protection of native birds. Such record shall be submitted and received into the case file for the associated discretionary action permitting the project.

Enforcement Agency: Los Angeles Department of Building and Safety

Monitoring Agency: Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Once, prior to issuance of building permit; or, if vegetation removal, building demolition or grading is initiated during the nesting season, as determined by a qualified biologist

Action Indicating Compliance: if vegetation removal, building demolition, or grading is initiated during the nesting season, submittal of a survey report by a qualified biologist.

IV-60 Tree Preservation (Grading Activities)

• "Orange fencing" or other similarly highly visible barrier shall be installed outside of the drip line of locally protected and significant (truck diameter of 8 inches or greater) non-protected trees, or as may be recommended by the Tree Expert. The barrier shall be maintained throughout the grading phase, and shall not be removed until the completion and cessation of all grading activities.

Enforcement Agency: Los Angeles Department of Building and Safety

Monitoring Agency: Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Ongoing during construction

Action Indicating Compliance: Issuance of Certificate of Occupancy or Land Use Permit

IV-70 Tree Removal (Non-Protected Trees) Environmental impacts from project implementation may result due to the loss of significant trees on the site. However, the potential impacts will be mitigated to a less than significant level by the following measures:

- Prior to the issuance of any permit, a plot plan shall be prepared indicating the location, size, type, and general condition of all existing trees on the site and within the adjacent public right(s)-of-way.
- All significant (8-inch or greater trunk diameter, or cumulative trunk diameter if multitrunked, as measured 54 inches above the ground) non-protected trees on the site proposed for removal shall be replaced at a 1:1 ratio with a minimum 24-inch box tree. Net, new trees, located within the parkway of the adjacent public right(s)-of-way, may be counted toward replacement tree requirements.
- Removal or planting of any tree in the public right-of-way requires approval of the Board of Public Works. Contact Urban Forestry Division at: 213-847-3077. All trees in the public right-of-way shall be provided per the current standards of the Urban Forestry Division the Department of Public Works, Bureau of Street Services.

Enforcement Agency: Board of Public Works Urban Forestry Division

Monitoring Agency: Board of Public Works Urban Forestry Division

Monitoring Phase: pre-construction

Monitoring Frequency: Once, at plan check, and once at field inspection

Action Indicating Compliance: Issuance of Certificate of Occupancy

IV-80 Tree Removal (Locally Protected Species) Environmental impacts may result due to the loss of protected trees on the site. However, these potential impacts will be mitigated to less than significant level by the following measures:

- All protected tree removals require approval from the Board of Public Works.
- A Tree Report shall be submitted to the Urban Forestry Division of the Bureau of Street Services, Department of Public Works, for review and approval (213-847-3077), prior to implementation of the Report's recommended measures.
- A minimum of two trees (a minimum of 48-inch box in size if available) shall be planted for each protected tree that is removed. The canopy of the replacement trees, at the time they are planted, shall be in proportion to the canopies of the protected tree(s) removed and shall be to the satisfaction of the Urban Forestry Division.
- The location of trees planted for the purposes of replacing a removed protected tree shall be clearly indicated on the required landscape plan, which shall also indicate the replacement tree species and further contain the phrase "Replacement Tree" in its description.
- Bonding (Tree Survival):
 - a. The applicant shall post a cash bond or other assurances acceptable to the Bureau of Engineering in consultation with the Urban Forestry Division and the decision maker guaranteeing the survival of trees required to be maintained, replaced or relocated in such a fashion as to assure the existence of continuously living trees for a minimum of three years from the date that the bond is posted or from the date such trees are replaced or relocated, whichever is longer. Any change of ownership shall require that the new owner post a new oak tree bond to the satisfaction of the Bureau of Engineering. Subsequently, the original owner's oak tree bond may be exonerated.
 - b. The City Engineer shall use the provisions of Section 17.08 as its procedural guide in satisfaction of said bond requirements and processing. Prior to exoneration of the bond, the owner of the property shall provide evidence satisfactory to the City Engineer and Urban Forestry Division that the oak trees were properly replaced, the date of the replacement and the survival of the replacement trees for a period of three years.

Enforcement Agency: Board of Public Works Urban Forestry Division

Monitoring Agency: Board of Public Works Urban Forestry Division

Monitoring Phase: Pre-Construction, Construction

Monitoring Frequency: Once during plan check, once during field inspection

Action Indicating Compliance: Issuance of Certificate of Occupancy

IV-90 Tree Removal (Public Right-of-Way)

- Removal of trees in the public right-of-way requires approval by the Board of Public Works.
- The required Tree Report shall include the location, size, type, and condition of all existing trees in the adjacent public right-of-way and shall be submitted for review and approval by

the Urban Forestry Division of the Bureau of Street Services, Department of Public Works (213-847-3077).

- The plan shall contain measures recommended by the tree expert for the preservation of as many trees as possible. Mitigation measures such as replacement by a minimum of 24-inch box trees in the parkway and on the site, on a 1:1 basis, shall be required for the unavoidable loss of significant (8-inch or greater trunk diameter, or cumulative trunk diameter if multitrunked, as measured 54 inches above the ground) trees in the public right-of-way.
- All trees in the public right-of-way shall be provided per the current Urban Forestry Division standards.

Enforcement Agency: Board of Public Works

Monitoring Agency: Board of Public Works Urban Forestry Division

Monitoring Phase: Pre-Construction, Construction

Monitoring Frequency: Once during plan check, once during field inspection

Action Indicating Compliance: Issuance of Certificate of Occupancy

VI. Geology and Soils

VI-20 Erosion/Grading/Short-Term Construction Impacts Short-term erosion impacts may result from the construction of the proposed project. However, these impacts can be mitigated to a less than significant level by the following measures:

• The applicant shall provide a staked signage at the site with a minimum of 3-inch lettering containing contact information for the Senior Street Use Inspector (Department of Public Works), the Senior Grading Inspector (LADBS) and the hauling or general contractor.

Enforcement Agency: Los Angeles Department of Building and Safety

Monitoring Agency: Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Ongoing during construction

Action Indicating Compliance: Issuance of Certificate of Occupancy or Land Use Permit

Green House Gas Emissions

Greenhouse Gas (architectural coatings):

Low- and non-VOC containing paints, sealants, adhesives, solvents, asphalt primer, and architectural coatings (where used), or pre-fabricated architectural panels shall be used in the construction of the Project to reduce VOC emissions to the maximum extent practicable.

Enforcement Agency: Los Angeles Department of Building and Safety; SCAQMD

Monitoring Agency: Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Periodic field inspections during construction

Action Indicating Compliance: Field inspection sign-off

Noise

XII-20 Increased Noise Levels (Demolition, Grading, and Construction Activities)

- Construction and demolition shall be restricted to the hours of 7:00 am to 6:00 pm Monday through Friday, and 8:00 am to 6:00 pm on Saturday.
- Demolition and construction activities shall be scheduled so as to avoid operating several pieces of equipment simultaneously, which causes high noise levels.
- The project contractor shall use power construction equipment with state-of-the-art noise shielding and muffling devices.

Enforcement Agency: Los Angeles Department of Building and Safety

Monitoring Agency: Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Ongoing during field inspection

Action Indicating Compliance: Issuance of Certificate of Occupancy or Use of Land

XII-40 Increased Noise Levels (Parking Structure Ramps)
Environmental impacts may result from project implementation due to noise from cars using the

parking ramp. However, the potential impacts will be mitigated to a less than significant level by the following measures:

- Concrete, not metal, shall be used for construction of parking ramps.
- The interior ramps shall be textured to prevent tire squeal at turning areas.
- Parking lots located adjacent to residential buildings shall have a solid decorative wall adjacent to the residential.

Enforcement Agency: Los Angeles Department Building and Safety

Monitoring Agency: Los Angeles Department of Building and Safety

Monitoring Phase: Pre-construction; Construction

Monitoring Frequency: Once, at plan check for Project; Once, during field inspection

Action Indicating Compliance: Plan approval and issuance of applicable building permit (Preconstruction); Issuance of Certificate of Occupancy of Use of Land (Construction)

Public Services

XIV-10 Public Services (Fire)

Environmental impacts may result from project implementation due to the location of the project in an area having marginal fire protection facilities. However, this potential impact will be mitigated to a less than significant level by the following measure:

The following recommendations of the Fire Department relative to fire safety shall be incorporated into the building plans, which includes the submittal of a plot plan for approval by the Fire Department either prior to the recordation of a final map or the approval of a building permit. The plot plan shall include the following minimum design features: fire lanes, where required, shall be a minimum of 20 feet in width; all structures must be within 300 feet of an approved fire hydrant, and entrances to any dwelling unit or guest room shall not be more than 150 feet in distance in horizontal travel from the edge of the roadway of an improved street approved fire lane.

Enforcement Agency: Los Angeles Department of Building and Safety

Monitoring Agency: Los Angeles Department of Building and Safety

Monitoring Phase: Pre-Construction

Monitoring Frequency: Once, at plan check

Action Indicating Compliance: Issuance of building permits

XIV-20 Public Services (Police – Demolition/Construction Sites)

Temporary construction fencing shall be placed along the periphery of the active construction areas to screen as much of the construction activity from view at the local street level and to keep unpermitted persons from entering the construction area.

Enforcement Agency: Los Angeles Department of building and Safety

Monitoring Agency: Los Angeles Department of building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Periodic field inspections during construction

Action Indicating Compliance: Field inspection sign-off

XIV-30 Public Services (Police)

Environmental impacts may result from project implementation due to the location of the project in an area having marginal police services. However, this potential impact will be mitigated to a less than significant level by the following measure:

• The plans shall incorporate the design guidelines relative to security, semi-public and private spaces, which may include but not be limited to access control to building, secured parking facilities, walls/fences with key systems, well-illuminated public and semi-public space designed with a minimum of dead space to eliminate areas of concealment, location of toilet facilities or building entrances in high-foot traffic areas, and provision of security guard patrol throughout the project site if needed. Please refer to "Design Out Crime Guidelines: Crime Prevention Through Environmental Design", published by the Los Angeles Police Department. Contact the Community Relations Division, located at 100 W. 1st Street, #250, Los Angeles, CA 90012; (213) 486-6000. These measures shall be approved by the Police Department prior to the issuance of building permits.

Enforcement Agency: Los Angeles Department of Building and Safety

Monitoring Agency: Los Angeles Department of Building and Safety

Monitoring Phase: Pre-Construction

Monitoring Frequency: Once, at plan check

Page

Action Indicating Compliance: Issuance of building permits

Public Utilities and Service Systems

XVII-50 Utilities (Local Water Supplies - Residential Condominium Conversion) Environmental impacts may result from project implementation due to the cumulative increase in demand on the City's water supplies. However, this potential impact will be mitigated to a less than significant level by the following measures:

- Install/retrofit high-efficiency toilets (maximum 1.28 gpf), including dual-flush water closets in all restrooms as appropriate.
- Install/retrofit restroom faucets with a maximum flow rate of 1.5 gallons per minute.
- Install/retrofit no more than one showerhead per shower stall, having a flow rate no greater than 2.0 gallons per minute.
- Install and utilize only high-efficiency clothes washers (water factor of 6.0 or less) in the project, if proposed to be provided in either individual units and/or in a common laundry room(s). If such appliance is to be furnished by a tenant, this requirement shall be incorporated into the lease agreement, and the applicant shall be responsible for ensuring compliance.
- Install and utilize only high-efficiency Energy Star-rated dishwashers in the project, if proposed to be provided. If such appliance is to be furnished by a tenant, this requirement shall be incorporated into the lease agreement, and the applicant shall be responsible for ensuring compliance.
- Enforcement Agency: Los Angeles Department of Building and Safety
- Monitoring Agency: Los Angeles Department of Building and Safety
- **Monitoring Phase:** Pre-construction
- Monitoring Frequency: Once, at plan check
- Action Indicating Compliance: Plan approval

Mandatory Findings of Significance

XVIII-10 Cumulative

Impacts

There may be environmental impacts which are individually limited, but significant when viewed in connection with the effects of past projects, other current projects, and probable future projects. However, these cumulative impacts will be mitigated to a less than significant level though compliance with the above mitigation measures.

XVIII-20 Effects on Human Beings

The project has potential environmental effects which cause substantial adverse effects on human beings, either directly or indirectly. However, these potential impacts will be mitigated to a less than significant level through compliance with the above mitigation measures.

XVIII-30 End

The conditions outlined in this proposed mitigated negative declaration which are not already required by law shall be required as condition(s) of approval by the decision-making body except as noted on the face page of this document. Therefore, it is concluded that no significant impacts are apparent which might result from this project's implementation.

Regulatory Compliance Measures

In addition to the Mitigation Measures required of the project, and any proposed Project Design Features, the applicant shall also adhere to any applicable Regulatory Compliance Measures required by law. Listed below is a list of often required Regulatory Compliance Measures. Please note that requirements are determined on a case by case basis, and these are an example of the most often required Regulatory Compliance Measures.

AESTHETICS

- Regulatory Compliance Measure RC-AE-3 (Vandalism): Compliance with provisions of the Los Angeles Building Code. The project shall comply with all applicable building code requirements, including the following:
 - Every building, structure, or portion thereof, shall be maintained in a safe and sanitary condition and good repair, and free from, debris, rubbish, garbage, trash, overgrown vegetation or other similar material, pursuant to Municipal Code Section 91.8104.
 - The exterior of all buildings and fences shall be free from graffiti when such graffiti is visible from a street or alley, pursuant to Municipal Code Section 91.8104.15.
- Regulatory Compliance Measure RC-AE-4 (Signage): Compliance with provisions of the Los Angeles Building Code. The project shall comply with the Los Angeles Municipal Code Section 91.6205, including on-site signage maximums and multiple temporary sign restrictions, as applicable.
- Regulatory Compliance Measure RC-AE-5 (Signage on Construction Barriers): Compliance with provisions of the Los Angeles Building Code. The project shall comply with the Los Angeles Municipal Code Section 91.6205, including but not limited to the following provisions:
 - The applicant shall affix or paint a plainly visible sign, on publically accessible portions of the construction barriers, with the following language: "POST NO BILLS".
 - Such language shall appear at intervals of no less than 25 feet along the length of the publically accessible portions of the barrier.
 - The applicant shall be responsible for maintaining the visibility of the required signage and for maintaining the construction barrier free and clear of any unauthorized signs within 48 hours of occurrence.

AIR QUALITY

- Regulatory Compliance Measure RC-AQ-1(Demolition, Grading and Construction Activities): Compliance with provisions of the SCAQMD District Rule 403. The project shall comply with all applicable standards of the Southern California Air Quality Management District, including the following provisions of District Rule 403:
 - All unpaved demolition and construction areas shall be wetted at least twice daily during excavation and construction, and temporary dust covers shall be used to reduce dust emissions and meet SCAQMD District Rule 403. Wetting could reduce fugitive dust by as much as 50 percent.
 - The construction area shall be kept sufficiently dampened to control dust caused by grading and hauling, and at all times provide reasonable control of dust caused by wind.
 - All clearing, earth moving, or excavation activities shall be discontinued during periods of high winds (i.e., greater than 15 mph), so as to prevent excessive amounts of dust.
 - All dirt/soil loads shall be secured by trimming, watering or other appropriate means to prevent spillage and dust.
 - All dirt/soil materials transported off-site shall be either sufficiently watered or securely covered to prevent excessive amount of dust.
 - General contractors shall maintain and operate construction equipment so as to minimize exhaust emissions.
 - o Trucks having no current hauling activity shall not idle but be turned off.
- Regulatory Compliance Measure RC-AQ-2: In accordance with Sections 2485 in Title 13 of the California Code of Regulations, the idling of all diesel-fueled commercial vehicles (weighing over 10,000 pounds) during construction shall be limited to five minutes at any location.
- Regulatory Compliance Measure RC-AQ-3: In accordance with Section 93115 in Title 17 of the California Code of Regulations, operation of any stationary, diesel-fueled, compression-ignition engines shall meet specified fuel and fuel additive requirements and emission standards.
- Regulatory Compliance Measure RC-AQ-4: The Project shall comply with South Coast Air Quality Management District Rule 1113 limiting the volatile organic compound content of architectural coatings.
- **Regulatory Compliance Measure RC-AQ-5:** The Project shall install odor-reducing equipment in accordance with South Coast Air Quality Management District Rule 1138.
- Regulatory Compliance Measure RC-AQ-6: New on-site facility nitrogen oxide emissions shall be minimized through the use of emission control measures (e.g., use of best available control technology for new combustion sources such as boilers and water

heaters) as required by South Coast Air Quality Management District Regulation XIII, New Source Review.

CULTURAL RESOURCES

- Regulatory Compliance Measure RC-CR-1 (Designated Historic-Cultural Resource): Compliance with United States Department of the Interior National Park Service Secretary of the Interior's Standards for the Treatment of Historic Properties. The project shall comply with the Secretary of the Interior's Standards for Historical Resources, including but not limited to the following measures:
 - o Prior to the issuance of any permit, the project shall obtain clearance from the Department of Cultural Affairs for the proposed work.
 - A property shall be used for its historic purpose or be placed in a new use that requires minimal change to the defining characteristics of the building and its site and environment.
 - o The historic character of a property shall be retained and preserved. The removal of historic material or alteration of features and spaces shall be avoided.
 - Each property shall be recognized as a physical record of its time, place and use. Changes that create a false sense of historical development, such as adding conjectural features or elements from other buildings, shall not be undertaken.
 - Most properties change over time; those changes that have acquired significance in their own right shall be retained and preserved.
- Regulatory Compliance Measure RC-CR-2 (Archaeological): If archaeological resources are discovered during excavation, grading, or construction activities, work shall cease in the area of the find until a qualified archaeologist has evaluated the find in accordance with federal, State, and local guidelines, including those set forth in California Public Resources Code Section 21083.2. Personnel of the proposed Modified Project shall not collect or move any archaeological materials and associated materials. Construction activity may continue unimpeded on other portions of the Project site. The found deposits would be treated in accordance with federal, State, and local guidelines, including those set forth in California Public Resources Code Section 21083.2.
 - o Distinctive features, finishes and construction techniques or examples of skilled craftsmanship which characterize an historic property shall be preserved.
 - Deteriorated historic features shall be repaired rather than replaced. Where the severity if deterioration requires replacement of a distinctive historic feature, the new feature shall match the old in design, color, texture, and other visual qualities, and where possible, materials. Replacement of missing features shall be substantiated by documentary, physical, or pictorial evidence.
 - Chemical or physical treatments, such as sandblasting, that cause damage to historic materials shall not be used. The surface cleaning of structures, if appropriate, shall be undertaken using the gentlest means possible.

- Significant archaeological resources affected by a project shall be protected and preserved. If such resources must be disturbed, mitigation measures shall be undertaken.
- New additions, exterior alterations, or related new construction shall not destroy historic materials that characterize the property. The new work shall be differentiated from the old and shall be compatible with the massing, size, scale, and architectural features to protect the historic integrity of the property and its environment.
- New additions and adjacent or related new construction shall be undertaken in such a manner that if removed in the future, the essential form and integrity of the historic property and its environment would be unimpaired.
- Regulatory Compliance Measure RC-CR-3 (Paleontological): If paleontological resources are discovered during excavation, grading, or construction, the City of Los Angeles Department of Building and Safety shall be notified immediately, and all work shall cease in the area of the find until a qualified paleontologist evaluates the find. Construction activity may continue unimpeded on other portions of the Project site. The paleontologist shall determine the location, the time frame, and the extent to which any monitoring of earthmoving activities shall be required. The found deposits would be treated in accordance with federal, State, and local guidelines, including those set forth in California Public Resources Code Section 21083.2.
- Regulatory Compliance Measure CR-4 (Human Remains): If human remains are encountered unexpectedly during construction demolition and/or grading activities, State Health and Safety Code Section 7050.5 requires that no further disturbance shall occur until the County Coroner has made the necessary findings as to origin and disposition pursuant to California Public Resources Code (PRC) Section 5097.98. In the event that human remains are discovered during excavation activities, the following procedure shall be observed:
 - Stop immediately and contact the County Coroner:

1104 N. Mission Road

Los Angeles, CA 90033

323-343-0512 (8 a.m. to 5 p.m. Monday through Friday) or

323-343-0714 (After Hours, Saturday, Sunday, and Holidays)

If the remains are determined to be of Native American descent, the Coroner has 24 hours to notify the Native American Heritage Commission (NAHC).

- o The NAHC will immediately notify the person it believes to be the most likely descendent of the deceased Native American.
- The most likely descendent has 48 hours to make recommendations to the owner, or representative, for the treatment or disposition, with proper dignity, of the human remains and grave goods.
- o If the owner does not accept the descendant's recommendations, the owner or the descendent may request mediation by the NAHC.

GEOLOGY AND SOILS

- Regulatory Compliance Measure RC-GEO-1 (Seismic): The design and construction of the project shall conform to the California Building Code seismic standards as approved by the Department of Building and Safety.
- Regulatory Compliance Measure RC-GHG-1 (Green Building Code): In accordance with the City of Los Angeles Green Building Code (Chapter IX, Article 9, of the Los Angeles Municipal Code), the Project shall comply with all applicable mandatory provisions of the 2013 Los Angeles Green Code and as it may be subsequently amended or modified.

HAZARDS AND HAZARDOUS MATERIALS

- Regulatory Compliance Measure RC-HAZ-1: Explosion/Release (Existing Toxic/Hazardous Construction Materials)
 - (Asbestos) Prior to the issuance of any permit for the demolition or alteration of the existing structure(s), the applicant shall provide a letter to the Department of Building and Safety from a qualified asbestos abatement consultant indicating that no Asbestos-Containing Materials (ACM) are present in the building. If ACMs are found to be present, it will need to be abated in compliance with the South Coast Air Quality Management District's Rule 1403 as well as all other applicable State and Federal rules and regulations.
 - (Lead Paint) Prior to issuance of any permit for the demolition or alteration of the existing structure(s), a lead-based paint survey shall be performed to the written satisfaction of the Department of Building and Safety. Should lead-based paint materials be identified, standard handling and disposal practices shall be implemented pursuant to OSHA regulations.
 - O (Polychlorinated Biphenyl Commercial and Industrial Buildings) Prior to issuance of a demolition permit, a polychlorinated biphenyl (PCB) abatement contractor shall conduct a survey of the project site to identify and assist with compliance with applicable state and federal rules and regulation governing PCB removal and disposal.

• Regulatory Compliance Measure RC-HAZ-2: Explosion/Release (Methane Zone): As the Project Site is within a methane zone, prior to the issuance of a building permit, the Site shall be independently analyzed by a qualified engineer, as defined in Ordinance No. 175,790 and Section 91.7102 of the LAMC, hired by the Project Applicant. The engineer shall investigate and design a methane mitigation system in compliance with the LADBS Methane Mitigation Standards for the appropriate Site Design Level which will prevent or retard potential methane gas seepage into the building. The Applicant shall implement the engineer's design recommendations subject to DOGGR, LADBS and LAFD plan review and approval.

HYDROLOGY AND WATER QUALITY

- Regulatory Compliance Measure RC-WQ-1: National Pollutant Discharge Elimination System General Permit. Prior to issuance of a grading permit, the Applicant shall obtain coverage under the State Water Resources Control Board National Pollutant Discharge Elimination System General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activities (Order No. 2009-0009-DWQ, National Pollutant Discharge Elimination System No. CAS000002) (Construction General Permit) for Phase 1 of the proposed Modified Project. The Applicant shall provide the Waste Discharge Identification Number to the City of Los Angeles to demonstrate proof of coverage under the Construction General Permit. A Storm Water Pollution Prevention Plan shall be prepared and implemented for the proposed Modified Project in compliance with the requirements of the Construction General Permit. The Storm Water Pollution Prevention Plan shall identify construction Best Management Practices to be implemented to ensure that the potential for soil erosion and sedimentation is minimized and to control the discharge of pollutants in stormwater runoff as a result of construction activities.
- Regulatory Compliance Measure RC-WQ-2: Dewatering. If required, any dewatering activities during construction shall comply with the requirements of the Waste Discharge Requirements for Discharges of Groundwater from Construction and Project Dewatering to Surface Waters in Coastal Watersheds of Los Angeles and Ventura Counties (Order No. R4-2008-0032, National Pollutant Discharge Elimination System No. CAG994004) or subsequent permit. This will include submission of a Notice of Intent for coverage under the permit to the Los Angeles Regional Water Quality Control Board at least 45 days prior to the start of dewatering and compliance with all applicable provisions in the permit, including water sampling, analysis, and reporting of dewatering-related discharges.
 - Regulatory Compliance Measure RC-WQ-3: Low Impact Development Plan. Prior to issuance of grading permits, the Applicant shall submit a Low Impact Development Plan and/or Standard Urban Stormwater Mitigation Plan to the City of Los Angeles Bureau of Sanitation Watershed Protection Division for review and approval. The Low Impact Development Plan and/or Standard Urban Stormwater Mitigation Plan shall be prepared consistent with the requirements of the Development Best Management Practices Handbook.

• Regulatory Compliance Measure RC-WQ-4: Development Best Management Practices. The Best Management Practices shall be designed to retain or treat the runoff from a storm event producing 0.75 inch of rainfall in a 24-hour period, in accordance with the Development Best Management Practices Handbook Part B Planning Activities. A signed certificate from a licensed civil engineer or licensed architect confirming that the proposed Best Management Practices meet this numerical threshold standard shall be provided.

LAND USE AND PLANNING

• Regulatory Compliance Measure RC-LU-1 (Slope Density): The project shall not exceed the maximum density permitted in Hillside Areas, as calculated by the formula set forth in Los Angeles Municipal Code Section 17.05-C (for tracts) or 17.50-E (for parcel maps).

NOISE

• Regulatory Compliance Measure RC-NO-1 (Demolition, Grading, and Construction Activities): The project shall comply with the City of Los Angeles Noise Ordinance No. 144,331 and 161,574, and any subsequent ordinances, which prohibit the emission or creation of noise beyond certain levels at adjacent uses unless technically infeasible.

TRANSPORTATION AND TRAFFIC

• Regulatory Compliance Measure RC-TT-1 (Increased Vehicle Trips/Congestion - West Side Traffic Fee) Prior to issuance of a Building Permit, the applicant shall pay a traffic impact fee to the City, based on the requirements of the West Los Angeles Traffic Improvement and Mitigation Specific Plan (WLA TIMP).

PUBLIC UTILITIES AND SERVICE SYSTEMS

Water Supply

• Regulatory Compliance Measure RC-WS-1 (Fire Water Flow) The Project Applicant shall consult with the LADBS and LAFD to determine fire flow requirements for the Proposed Project, and will contact a Water Service Representative at the LADWP to order a SAR. This system hydraulic analysis will determine if existing LADWP water supply

facilities can provide the proposed fire flow requirements of the Project. If water main or infrastructure upgrades are required, the Applicant would pay for such upgrades, which would be constructed by either the Applicant or LADWP.

• Regulatory Compliance Measure RC-WS-4 (Landscape) The Project shall comply with Ordinance No. 170,978 (Water Management Ordinance), which imposes numerous water conservation measures in landscape, installation, and maintenance (e.g., use drip irrigation and soak hoses in lieu of sprinklers to lower the amount of water lost to evaporation and overspray, set automatic sprinkler systems to irrigate during the early morning or evening hours to minimize water loss due to evaporation, and water less in the cooler months and during the rainy season).

Energy

• Regulatory Compliance Measure RC-EN-1(Green Building Code): The Project shall implement all applicable mandatory measures within the LA Green Building Code that would have the effect of reducing the Project's energy use.

Solid Waste

- Regulatory Compliance Measure RC-SW-1 (Designated Recycling Area) In compliance with Los Angeles Municipal Code, the proposed Modified Project shall provide readily accessible areas that serve the entire building and are identified for the depositing, storage, and collection of nonhazardous materials for recycling, including (at a minimum) paper, corrugated cardboard, glass, plastics, and metals.
- Regulatory Compliance Measure RC-SW-2 (Construction Waste Recycling) In order to meet the diversion goals of the California Integrated Waste Management Act and the City of Los Angeles, which will total 70 percent by 2013, the Applicant shall salvage and recycle construction and demolition materials to ensure that a minimum of 70 percent of construction-related solid waste that can be recycled is diverted from the waste stream to be landfilled. Solid waste diversion would be accomplished though the on-site separation of materials and/or by contracting with a solid waste disposal facility that can guarantee a minimum diversion rate of 70 percent. In compliance with the Los Angeles Municipal Code, the General Contractor shall utilize solid waste haulers, contractors, and recyclers who have obtained an Assembly Bill (AB) 939 Compliance Permit from the City of Los Angeles Bureau of Sanitation.